

**BID FORM**

**IFB #B41-133**

**Revised per Addendum #4**

**HENSON CREEK GOLF COURSE BRIDGE REPLACEMENT**

The undersigned hereby certifies that bidder has examined and fully comprehends the requirements and intent of the plans, and specifications and addendum

Number \_\_\_\_\_ Dated \_\_\_\_\_ Number \_\_\_ Dated \_\_\_\_\_

for the above project; that the bidder has reviewed the supplied drawings and specifications, visited the site and examined all conditions affecting the work and proposes to furnish all labor, supervision, material, tools, equipment, engineering, supervision, etc., necessary for or incidental to, the proper execution of the work.

Signature: \_\_\_\_\_ Date \_\_\_\_\_

Name & Title (type or print) \_\_\_\_\_

Business Name \_\_\_\_\_

Address \_\_\_\_\_

Telephone Number \_\_\_\_\_ Fax Number \_\_\_\_\_ E-Mail \_\_\_\_\_

(Optional) Prompt Payment Discount: \_\_\_\_\_%; twenty days; net 30 days.

Supply all labor, supervision, materials and equipment to replace the pedestrian / cart bridge and all associated work in accordance with the drawings and specification.						
Item No.	Specification No.	Description	Qty.	Unit	Unit Price	Total Price
1	Div. 1	Weekly Cleanup	1	LS		
2	Div. 1	Final Cleanup	1	LS		
3	Div. 1	Temporary Signage	1	LS		
4	Div. 1	Mobilization and Maintenance of Traffic	1	LS		

5	Div. 1	Scaffolding during bridge installation	1	LS		
6	spec 504	Asphalt, 3" thick (large volume)	180	SY		
7	spec 511	RC-6 Subbase	6	TON		
8	spec 200	Earthwork Cut / Fill over 0.5 acre site	2,515	CY		
9	Div. 2	Remove impervious pavement	2,187	SF		
10	Div. 2	Remove bituminous pavement	243	SY		
11	Div. 2	Remove aggregate base	243	SY		
12	Div. 2	Bridge demolition, steel, 50' to 160' long, 12' wide	1,400	SF		
13	Div. 2	Remove site utility lines - 15" HDPE	13	LF		
14	Div. 2	Hauling and disposal	20	ROUND TRIPS		
15	Div. 2	Disposal fees	240	CY		
16	Div. 3	Concrete footing for Abutment & wing wall, includes reinforcements and formwork	26	CY		
17	Div. 3	Concrete foundation wall for Abutment, includes reinforcements and formwork	14	CY		
18	Div. 3	Concrete foundation wall for wing wall, includes reinforcements and formwork	8	CY		
19	Div. 3	6" slab on metal deck, including reinforcement	1,560	SF		
20	Div. 3	Hardened floor finish	1,560	SF		
21	Div. 31	Temporary Barrier Diversion	240	LF		

22	Div. 31	Site clearing & Grubbing including tree removal	0.2	AC		
23	Div. 31	Site rough grading (cut)	261	CY		
24	Div. 31	Site fine grading	6,002	SF		
25	Div. 31	Super silt fence	343	LF		
26	Div. 31	Diversion fence	263	LF		
27	Div. 31	Mountable berm	56	SF		
28	Div. 31	No. 57 Stone	167	CY		
29	Div. 31	Stabilized construction entrance	1,156	SF		
30	Div. 31	Steel Pile, HP 12x63	650	VLF		
31	Div. 31	Excavations	556	CY		
32	Div. 31	Backfilling and compaction	389	CY		
33	Div. 31	Hauling and disposal	20	ROUND TRIPS		
34	Div. 31	Soils Disposal fees	235	CY		
35	Div. 31	Channel Sand & Gravel, Granular Filter	385	CY		
36	Div. 31	Cross Vane Stones	163	CY		
37	Div. 31	Rifle Grade Control Material	113	CY		
38	Div. 31	Rip Rap for Channel Bed	150	CY		
39	Div. 31	Filter Bag	4	EA		
40	Div. 31	Natural Fiber Matting	420	SY		
41	Div. 31	Filter Cloth	166	SY		
42	Div. 31	Geotextile Fabric	1,574	SF		
43	Div. 32	Impervious pavement, includes base	1,456	SF		

44	Div. 32	Asphalt pavement, includes base Steel Bridge:	165	SY		
45	Div. 32	Bridge shop drawings & submittal package including all required resubmittals to receive approval and approved building permit	1	LS		
46	Div. 32	Prefabricated steel bridge, 120' long, 12' wide, with safety railing and steel toe plate	120	LF		
47	Div. 32	Metal slab form, 20 ga.	1,560	SF		
48	Div. 32	Third party testing	1	LS		
49	Div. 32	Topsoil	1,556	SY		
50	Div. 32	Ernst Seed mix	1	LB		
51	Div. 32	Shrubs	10	EA		
52	Div. 32	Live Stakes	252	EA		
53	Div. 32	New trees	6	EA		
54	Div. 32	Allowance for miscellaneous unforeseen exterior improvement	1	LS	\$10,000	
55	Div. 32	Dewatering Pipe	132	LF		
56	Div. 32	Clear water diversion Pipe, 12" dia., including trench work	85	LF		
57	Div. 32	Clear water diversion Pipe, 15" dia., including trench work	22	LF		
58	Div. 32	Dewatering Pump	1	EA		
59		Allowance for DPIE mandated changes between 90% CD and permit drawings	1	LS	\$16,000	

60		Allowance for unforeseen / changing stream conditions	1	LS	\$10,000	
61	Contingency	Contingency: Unforeseen site conditions and impacts to construction	1	LS	\$20,000	
62	Contingency	Contingency: trail and parking lot asphalt/pavement repair/replacement	1	LS	\$30,000	
<b>Total Bid:</b>						
Written: (Do Not Round Off Numbers)				Numerical \$		